

Date: March 15, 2017

Project: Copper Sky Amphitheater and Pool

Maricopa, AZ

Ref: 176810

NATIONAL JOINT POWERS ALLIANCE – NJPA

Master Project: 170558, **Contract Number:** 082114-msl, **Expiration:** 09/16/2018

Category: Facility & MRO, **Sub-Category:** Athletic Field / Court and Parking Lot Lighting Systems

Quotation Price – Materials Delivered to Job Site and Installation

Copper Sky Amphitheater and Pool\$241,500

Light-Structure System with Total Light Control – TLC for LED™ technology

System Description

- (6) Pre-cast concrete bases with integrated lightning grounding
- (6) Galvanized steel poles
- Factory wired and tested remote electrical component enclosures
- Pole length, factory assembled wire harnesses
- Factory wired poletop luminaire assemblies
- (22) Factory aimed and assembled luminaries
- UL Listed as a complete system

Control Systems and Services

- Control-Link® System for remote on/off control and performance monitoring with 24/7 customer support

Operation and Warranty Services

- Reduction of energy and maintenance costs by 50% to 85% over typical 1500W metal halide equipment
- Product assurance and warranty program that covers materials and onsite labor, eliminating 100% of your maintenance costs for 25 years
- Support from Musco's Lighting Services Team – over 170 Team members dedicated to operating and maintaining your lighting system – plus a network of 1800+ contractors

Payment Terms – Per Musco Credit Department

Email or fax a copy of the Purchase Order to Musco Sports Lighting, LLC:

Musco Sports Lighting, LLC

Attn: Dee Smith

Fax: 800-374-6402

Email: musco.contracts@musco.com

All purchase orders should note the following:

National Joint Powers Alliance-NJPA purchase – Contract Number: 082114-MSL

Delivery Timing

6 - 8 weeks for delivery of materials to the job site from the time of order, submittal approval, and confirmation of order details including voltage, phase, and pole locations.

Due to the built-in custom light control per luminaire, pole locations need to be confirmed prior to production. Changes to pole locations after the product is sent to production could result in additional charges.



Notes

Quote is based on:

- Shipment of entire project together to one location
- 480 Volt, 3 Phase electrical system requirement
- Structural code and wind speed = 2012 IBC, 115 MPH
- Owner is responsible for getting electrical power to the site, coordination with the utility, and any power company fees
- Standard soil conditions – rock, bottomless, wet or unsuitable soil may require additional engineering, special installation methods and additional cost
- Confirmation of pole locations prior to production

Thank you for considering Musco for your lighting needs. Please contact me with any questions or need additional details.

Dee Smith

Musco Sports Lighting, LLC

Phone: 480-521-8271

E-mail: dee.smith@musco.com

