

Sanitary Sewer Exhibit C
Engineer's Construction Cost Estimate
City of Maricopa
Public Works Fire Maintenance Facility

Item Number	Description	Unit	Quantity	Unit Price	Cost
1	5' Diameter Sanitary Sewer Manhole per MAG Detail 420	EA	2	\$5,000.00	\$ 10,000.00
2	8" PVC SDR-35 Sanitary Sewerline	LF	238	\$55.00	\$ 13,080.00
3	Pipe Plug per Global Water Detail 450	EA	1	\$120.00	\$ 120.00
4	Remove Existing Sanitary Sewer Cleanout	EA	1	\$100.00	\$ 100.00
5	Remove Existing 12" Sanitary Sewerline	EA	53	\$20.00	\$ 1,080.00
Total Sanitary Sewer =					\$ 24,370.00

