


ELECTRICAL SITE PHOTOMETRY PLAN

SCALE: 1" = 30'-0"



STATISTICS						
DESCRIPTION	SYMBOL	AVG	MAX	MIN	MAX/MIN	AVG/MIN
SITE LIGHTING	+	1.9 FC	48.7 FC	0.0 FC	N/A	N/A

SCHEDULE									
SYMBOL	LABEL	MANUFACTURER	CATALOG	DESCRIPTION	LAMP	LAMP OUTPUT	LLF	TOTAL OUTPUT	INPUT POWER
—	SL6	NEW ALIGHT	LIN 3 SP 9FT LS 35 U ASY M T D	36' LENGTH OF LINO SLIM LS WW MOUNTED TO MULLION AT 8'6" VERIFY EXACT LENGTH WITH ARCHITECT	LED - 3500K COLOR TEMP	1623	1	14608	171
—	SL6	NEW ALIGHT	LIN 3 SP 224FT LS 35 U ASY M T D	224' LENGTH OF LINO SLIM LS WW MOUNTED TO MULLION AT 8'6" VERIFY EXACT LENGTH WITH ARCHITECT	LED - 3500K COLOR TEMP	1623	1	90897	1064
—	SL6	NEW ALIGHT	LIN 3 SP 80FT LS 35 U ASY M T D	80' LENGTH OF LINO SLIM LS WW MOUNTED TO MULLION AT 8'6" VERIFY EXACT LENGTH WITH ARCHITECT	LED - 3500K COLOR TEMP	1623	1	32463	380
—	SL6	NEW ALIGHT	LIN 3 SP 140FT LS 35 U ASY M T D	140' LENGTH OF LINO SLIM LS WW MOUNTED TO MULLION AT 8'6" VERIFY EXACT LENGTH WITH ARCHITECT	LED - 3500K COLOR TEMP	1623	1	56810	665
—	SL6	NEW ALIGHT	LIN 3 SP 20FT LS 35 U ASY M T D	20' LENGTH OF LINO SLIM LS WW MOUNTED TO MULLION AT 8'6" VERIFY EXACT LENGTH WITH ARCHITECT	LED - 3500K COLOR TEMP	1623	1	8116	95
—	SL6	NEW ALIGHT	LIN 3 SP 128FT LS 35 U ASY M T D	128' LENGTH OF LINO SLIM LS WW MOUNTED TO MULLION AT 8'6" VERIFY EXACT LENGTH WITH ARCHITECT	LED - 3500K COLOR TEMP	1623	1	51941	608
△	SL4	NEW & EXIST BEGA	2192LED SLV K4	MATCH EXISTING STEP LIGHT MOUNTED VERTICALLY (IN BOLLARD COLUMN BY OTHERS)	LED - 4000K COLOR TEMP	96	0.91	96	11.3
□ ■	SLA	NEW & EXIST LITHONIA	DSX0 LED P4 40K 70CRI TFTM / SSS 20'	MATCH EXISTING D-SERIES SIZE 0 AREA LUMINAIRE P4 PERFORMANCE PACKAGE 4000K CCT 70 CRI FORWARD THROW	LED - 4000K COLOR TEMP	11374	0.91	11374	93.04
□ ■	SLC	NEW LITHONIA	DSX2 LED P2 40K 70CRI T3M / SSS 30'	MATCH EXISTING AT REC CENTER D-SERIES SIZE 2 AREA LUMINAIRE P2 PERFORMANCE PACKAGE 4000K CCT 70 CRI TYPE 3 MEDIUM	LED - 4000K COLOR TEMP	24924	0.91	24924	179.22
□ ■	SLD	NEW LITHONIA	DSX0 LED P4 40K 70CRI T3M / SSS 20'	MATCH EXISTING D-SERIES SIZE 0 AREA LUMINAIRE P4 PERFORMANCE PACKAGE 4000K CCT 70 CRI TYPE 3 MEDIUM	LED - 4000K COLOR TEMP	11130	0.91	11130	93.04
□ ■	X	EXISTING STREET LIGHT	ESTIMATE FOR EXISTING STREET LIGHT @ 30'	ESTIMATE FOR EXISTING STREET LIGHT @ 30' AFG	UNKNOWN	18396	0.91	18396	171
□	SL5	EXISTING LITHONIA	DSXW1 LED 20C 700 30K T2M MVOLT	DSXW1 LED WITH 2 LIGHT ENGINES, 20 LED'S, 700MA DRIVER, 3000K LED, TYPE 2 MEDIUM OPTIC	LED - 4000K COLOR TEMP	3316	0.91	3316	47
□ ■	SLB	EXISTING LITHONIA	DSX2 LED 100C 700 40K TFTM MVOLT HS / SSS 20'	DSX2 LED WITH 100 LEDS @700MA, 4000K, TYPE FORWARD THROW MEDIUM OPTICS, WITH HOUSE SIDE SHIELD	LED - 4000K COLOR TEMP	21523	0.91	21523	232

DRAWN BY: CRG
JOB NO: 2405.000
DATE: 02/28/25
REVISIONS

ELECTRICAL SITE PHOTOMETRY PLAN

E1.3

SITE DEVELOPMENT

