



December 15, 2025

Maricopa Fire and Medical
20340 N. Estrella Parkway
Maricopa, AZ 85139
Andrew Boland
andrew.boland@maricopa-az.gov

We at Fire Truck Solutions are pleased to quote the following:

(1) E-One Typhoon Custom Cab Chassis HP100 100' Platform Demo Available September 2026 SO#146496:

- Typhoon Chassis Medium Cab
- Cummins X12 500 HP Engine
- Color Red Lower/Black Upper
- Allison EVS4000 Transmission
- Manual Windows
- Vista Display Drivers Side Dash
- 54,000# Meritor Axles
- 24,000# Dana Front Axle
- Alcoa Aluminum Dura-Black Wheels
- Bendix AD-9 Air Dryer
- Jacobs Compression Brake
- Combination Slam Style and Painted ROM Roll Up Doors
- Racor Fuel Water Separator
- 911 Seating FTS Retrofit Adding (2) Additional SCBA Folding Seats Rear Wall.
- (FTS) Emergency Lighting Changes (2) Lights from Green to Red/White Split M6
- (FTS) Add Red/Blue Light Pods to Whelen Mini Light Bars
- Blue Sea Model P12, 40 Amp Charger
- Blue Sea Sure Eject Receptacle 20 Amp
- USB Charging Ports in Cab
- Alco-Lite Ladder Compliment Included
- LED Lighting
- Multiplexing System
- Shelving and Trays
- 100' Aerial Ladder Assembly W/Platform
- Wheel Well Body Storage
- Safety Vision Backup Camera
- Safety Vision Drivers and Officers Side Camera
- Hale QMAX 2000 GPM Pump
- Class 1 TPG Plus Pressure Governor
- 300 Gallon Water Tank

(Please see complete Spec for all Options)



Base Truck Cost: \$2,272,989.00

Phoenix Sales Tax: \$188,603.00

Total Truck Cost: \$2,461,592.00

**Total Cost includes \$25,000.00 Contingency Funds*

Optional Add-On Items Included in Cost Shown completed at Fire Truck Solutions and E-One Factory-

- Remove standard folding seats and replace with matching 911 folding style SCBA seating at the rear wall, install SCBA Smart Dock Style SCBA brackets in seat backs, reinstall all seat belts and seat belt sensors.

Cost: \$7500.00

- Add 110V Shoreline AC system installed between forward rear wall seating, once seating installs are complete, install roof mounted AC condenser on the officer's side cab roof next to aerial, program into truck protection so that condenser cannot be hit by aerial.

Cost: \$14,500.00

****Note for 110V AC System we are awaiting approval from the supplier as to what system is to be used, due to this truck being a platform, there is not a great deal of real estate on the cab roof. The truck being quoted is a medium cab, we are not certain there will be enough room in the cab for the installation of the evaporator and controls. Cost for this installation is shown but further research will be needed to check dimensions. Cost shown is an estimate.***

- Add air ride SCBA seat in place of standard hard mount SCBA seating, involves the cutting of the front seat pedestal by 2" to reduce height to accommodate headroom for air ride seating requested. This modification will be completed at Fire Truck Solutions in Phoenix, when the truck arrives.

Cost: \$8,550.00

- Add Setcom (6) wired (1) wireless intercom system to the unit upon delivery, cost for the system and headsets are as follows, this system will be installed at the E-One factory in Ocala.

Cost: \$12,500.00

- Customer has requested that a compartment be added to the front of the side stacker hosebed area on the officer's side of the truck, this modification could not be completed because it would involve body modifications that the truck is past the point in production.

N/A



- Add divider in hosebed separating supply line and 2 1/2" deadload hose storage in the hosebed, this will reduce the original 1000' of supply to around 500' this divider will be installed by Fire Truck Solutions in Phoenix AZ when the unit arrives.
Cost: \$2,500.00
- Customer has asked that the front license plate holder be removed from the front bumper, this will be removed at Fire Truck Solutions location when the truck arrives, this will be a \$250.00 credit to Maricopa for the removal.
Credit: - \$250.00
- Remove rollout tray in L2 compartment, removal will be completed at Fire Truck Solutions in Phoenix when the truck arrives.
Cost: \$0.00
- Remove RH and LH front cowl mounted cameras, from the truck. This removal will take place during production of the unit at the E-One factory in Ocala.
Credit: -\$2,370.00
- Paint upper portion of cab, aerial sign plates and air conditioning condenser cover on cab roof (FLNA71010 Grey) to match existing Maricopa Fire fleet, this painting will take place during production at the E-One facility in Ocala Florida.
Cost: \$10,000.00
- Add Tomar Strobecon II emitter to cab roof and add Tomar Strobe emitter pack to upper captains' overhead compartment in cab, this installation will take place at the Fire Truck Solutions location in Phoenix, when the truck arrives.
Cost: \$2,850.00
- Remove beacon style lighting over L1/R1 compartment, install diamond plate fabricated boxes to accommodate (2) red Whelen M6 LED red lighting in original beacon location one officer and one driver side upper body. This installation fabrication and programming of flash pattern and switch install will be completed at the FTS facility upon the unit's arrival to Phoenix.
Cost: \$3,860.00
- Add two Firetech 18" single row LED scene lights to upper body above L1/R1 compartment next to the M6 LED emergency lighting, fabricate diamond plate covers so that lights are not stepped or damaged when working from the upper body, the installation fabrication of covers and switch installation will be completed by FTS when the unit arrives in Phoenix.
Cost: \$7,850.00



- Remove beacon style lights from the rear upper body and install (2) M6 Red/Amber Blue/Amber LED lights in the original beacon location, removal of original lighting as well as installation, flash pattern programming and switch installation will be completed at FTS upon the unit's arrival to Phoenix.

Cost: \$2,380.00

- Customer has requested that a double crosslay front bumper be added to the unit in place of the already quoted bumper, this unit was not originally equipped with a crosslay front bumper, therefore suspension is not of the capacity to carry the additional weight of the front bumper. This option will not be able to be completed at this stage in production.

N/A

- Add additional (10) red and blue light pods to the already quoted and installed mini lightbars on the unit, customer is concerned that there is not enough red/blue lighting for visibility. Disassembly of light bars and installation of additional pods is to be complete at the FTS facility when the unit arrives in Phoenix.

Cost: \$3,240.00

- Remove the Akron 1250 GPM monitor from platform, install Akron 2000 GPM capable monitor at and Nozzle at front of platform, complete all programming.

Cost: \$17,220.00

- Add AM/FM radio with weather band and Bluetooth function to the upper overhead console as well as add two additional speakers to the rear crew area in addition to the two speakers that will be installed in the side walls just above the officers and driver's locations. The installation and wiring of the AM/FM radio with Bluetooth will be completed at the FTS facility when the unit arrives in Phoenix.

Cost: \$2,500.00

**Quote valid for 60 days.*

**Truck available September 2026.*

**Cost shown includes truck freight.*

**Cost shown includes inspection trips for (4) Maricopa Fire Personnel.*

**Sourcewell Contract Pricing*

Mark Julien

Mark Julien
Apparatus Sales
Fire Truck Solutions

Customer Acceptance