
RE-PLAT TRACT Q1

"RANCHO EL DORADO PHASE III-PARCEL 33"

AS RECORDED IN CABINET F, SLIDE 187 PINAL COUNTY RECORDS, LYING WITHIN THE WEST HALF OF SECTION 13, TOWNSHIP 4 SOUTH, RANGE 3 EAST, GILA AND SALT RIVER MERIDIAN, CITY OF MARICOPA, PINAL COUNTY, ARIZONA



DEDICATION:

STATE OF ARIZONA	} S.S.
COUNTY OF PINAL	\$ 3.3
KNOW ALL MEN BY THESE	DRESENTS.

KNOW ALL MEN BY THESE PRESENTS:

CITY OF MARICOPA, A MUNICIPAL CORPORATION, AS OWNER, HEREBY PUBLISHES THIS RE-PLAT MAP LOCATED IN A PORTION OF THE WEST HALF OF SECTION 13, TOWNSHIP 4 SOUTH, RANGE 3 EAST OF, THE GILA AND SALT RIVER MERIDIAN, CITY OF MARICOPA, PINAL COUNTY, ARIZONA AS SHOWN AND PLATTED HEREON. THIS MAP SETS FORTH THE LOCATION AND GIVES THE DIMENSIONS OF THE LOTS CONSTITUTING SAME AND THAT THE LOTS SHALL BE KNOWN BY THE NUMBER OR NAME GIVEN EACH RESPECTIVELY ON SAID MAP.

IN WITNESS WHEREOF:

CITY OF MARICOPA, A MUNICIPAL CORPORATION, AS OWNER, HAS HEREUNTO CAUSED ITS NAME TO BE AFFIXED AND HAS EXECUTED THIS RE-PLAT MAP BY THE SIGNATURE OF THE UNDERSIGNED, DULY

AUTHORIZED THIS	DAY OF	2021
CITY OF MARICOPA, A	MUNICIPAL CORPORATION	
DV		

ITS AUTHORIZED REPRESENTITIVE

NOTARY PUBLIC

ACKNOWI FDGFMFNIT

MY COMMISSION EXPIRES:

<u>/(CIXI 40 4</u>	V LLD GLI II	
STATE OF ARIZONA	22 (
COUNTY OF PINAL	§ S.S.	
	DAY OFSONALLY APPEARED	2021, BEFORE ME, WHO
OF MARICOPA, A MUNIC	CIPAL CORPORATION, AND NITITIES, EXECUTED THIS RE	OF THE CITY BEING AUTHORIZED TO DO SO E-PLAT MAP FOR
IN WITNESS THEREOF. I	HAVE HEREUNTO SET MY	' HAND AND OFFICIAL SEAL.

LEGAL DESCRIPTION (PARENT PARCELS)

TRACT Q1, AS SHOWN ON THE "RANCHO EL DORADO PHASE III, PARCEL 33" FINAL PLAT RECORDED IN CABINET F, SLIDE 187, PINAL COUNTY RECORDS, BEING WITHIN A PORTION OF SECTION 13, TOWNSHIP 4 SOUTH, RANGE 3 EAST, PINAL COUNTY, ARIZONA.

LEGAL DESCRIPTION (NEW PARCEL)

TRACT Q1, AS SHOWN ON THE "RANCHO EL DORADO PHASE III, PARCEL 33" FINAL PLAT RECORDED IN CABINET F, SLIDE 187, PINAL COUNTY RECORDS, BEING WITHIN A PORTION OF SECTION 13, TOWNSHIP 4 SOUTH, RANGE 3 EAST, PINAL COUNTY, ARIZONA, BEING MORE PARTICULARLY DESCRIBED AS:

TRACT Q1 OF A FINAL PLAT "RANCHO EL DORADO PHASE III-PARCEL 33", RECORDED IN CABINET F, SLIDE 187 OF PINAL COUNTY RECORDS, AND LYING WITHIN THE WEST HALF OF SECTION 13, TOWNSHIP 4 SOUTH, RANGE 3 EAST, OF THE GILA AND SALT RIVER MERIDIAN, PINAL, ARIZONA, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT A BRASS CAP FLUSH "CITY OF MARICOPA" AT THE INTERSECTION PLACONE LANE & POWERS PARKWAY, SHOWN ON THE AFORE MENTIONED FINAL PLAT;

THENCE SOUTH 69 DEGREES 46 MINUTES 30 SECONDS WEST. 182.14 FEET ALONG THE CENTERLINE OF PLACONE LANE;

THENCE LEAVING SAID CENTERLINE, SOUTH 20 DEGREES 13 MINUTES 30 SECONDS EAST, 20.50 FEET TO A POINT ON THE SOUTH RIGHT-OF-WAY LINE OF PLACONE LANE AND THE POINT OF BEGINNING:

THENCE NORTH 69 DEGREES 46 MINUTES 30 SECONDS EAST ALONG SAID SOUTH RIGHT-OF-WAY LINE, A DISTANCE OF 96.64 FEET;

THENCE SOUTH 20 DEGREES 12 MINUTES 47 SECONDS EAST, A DISTANCE OF 60.00 FEET;

THENCE NORTH 69 DEGREES 46 MINUTES 30 SECONDS EAST, A DISTANCE OF 65.00 FEET TO A POINT ON THE WEST RIGHT-OF-WAY LINE OF POWERS PARKWAY:

THENCE SOUTH 20 DEGREES 12 MINUTES 47 SECONDS EAST, 730.82 FEET ALONG A LINE THAT IS PARALLEL AND 20.50 FEET WEST OF THE CENTERLINE OF POWERS PARKWAY, TO A TANGENT CURVE, CONCAVE WESTERLY, HAVING A RADIUS OF 979.50 FEET;

THENCE SOUTHEASTERLY ALONG SAID CURVE, THROUGH A CENTRAL ANGLE OF 05 DEGREES 42 MINUTES 41 SECONDS, AND AN ARC LENGTH OF 97.64 FEET TO A NON-TANGENT LINE;

THENCE NORTH 89 DEGREES 38 MINUTES 27 SECONDS WEST, 619.88 FEET;

THENCE NORTH 00 DEGREES 16 MINUTES 20 SECONDS EAST, 762.79 FEET TO A NON-TANGENT CURVE, CONCAVE TO THE LEFT, HAVING A RADIUS OF 520.50 FEET, THE CENTER OF WHICH BEARS NORTH 01 DEGREES 55 MINUTES 09 SECONDS WEST;

THENCE NORTHEASTERLY ALONG SAID CURVE, THROUGH A CENTRAL ANGLE OF 18 DEGREES 17 MINUTES 06 SECONDS, AND AN ARC LENGTH OF 166.11 FEET TO A TANGENT LINE TO THE POINT OF BEGINNING.

SAID PORTION OF LAND CONTAINING 385,416 SQUARE FEET, OR 8.8479 ACRES, MORE OR LESS, AND BEING SUBJECT TO ANY EASEMENTS, RESTRICTIONS, AND/OR RIGHTS-OF-WAYS OF RECORD OR OTHERWISE.

THIS DESCRIPTION SHOWN HEREON IS NOT TO BE USED TO VIOLATE SUBDIVISION REGULATIONS OF THE STATE, COUNTY AND/OR MUNICIPALITY, OR ANY OTHER LAND DIVISION RESTRICTIONS.

ASSURED WATER SUPPLY

THE ARIZONA DEPARTMENT OF WATER RESOURCES HAS GRANTED A CERTIFICATE OF ASSURED WATER SUPPLY, ARIZONA DEPARTMENT OF WATER RESOURCES FILE NO. 26-400804, FOR THE SUBDIVISION IN ACCORDANCE WITH SECTION 45-576 OF THE ARIZONA REVISED STATUES (ARS).

NOTES

- 1. A TITLE REPORT WAS NOT PROVIDED AT TIME OF SURVEY.
- 2. ALL DIMENSIONS SHOWN HEREON ARE MEASURED UNLESS OTHERWISE NOTED.
- 3. SURVEYOR MAKES NO GUARANTEE FOR ANY NON-VISIBLE RIGHTS-OF-WAY OR EASEMENTS NOT SHOWN IN PUBLIC RECORD.
- 4. NO STRUCTURE SHALL BE CONSTRUCTED IN NOR SHALL OTHER IMPROVEMENTS OR ALTERATIONS BE MADE TO THE STORM WATER RETENTION/DETENTION AREAS OR TO DRAINAGE EASEMENTS WITHOUT PRIOR APPROVAL BY THE CITY OF MARICOPA.
- STORM WATER RETENTION VOLUMES REQUIRED BY THE CITY OF MARICOPA DRAINAGE ORDINANCE HAVE BEEN MET AND THE OVERALL GROSS RETENTION/DETENTION VOLUMES WILL NOT BE CHANGED WITHOUT PRIOR APPROVAL BY THE CITY OF MARICOPA. MAINTENANCE OF THE AREAS SUBJECT TO STORM WATER RETENTION/DETENTION SHALL BE THE RESPONSIBILITY OF THE LOT OR TRACT OWNER.
- 6. ALL NEW OR RELOCATED UTILITIES SHALL BE PLACED UNDERGROUND.
- 7. MAINTENANCE OF ALL LANDSCAPING SHALL BE THE RESPONSIBILITY OF THE LAKES AT RANCHO EL DORADO HOMEOWNERS ASSOCIATION.
- 8. ALL WORK WITHIN THE PUBLIC RIGHTS-OF-WAY REQUIRE PERMITS AND INSPECTIONS BY THE CITY OF MARICOPA
- 9. ALL TRENCH WORK WITHIN THE PUBLIC UTILITY EASEMENTS REQUIRE PERMITS AND INSPECTIONS BY THE CITY OF MARICOPA.
- 10. ON ALL LOTS THE OWNER AND/OR THE DEVELOPER SHALL ENSURE THAT RESIDENTIAL DWELLINGS FIT WITHIN THE BUILDING SETBACKS INCLUDING BAY WINDOWS, FIREPLACES, PORCHES, COVERED PATIOS, ETC.
- 11. ALL EASEMENTS ARE SUBORDINATE TO THE DRAINAGE EASEMENTS.
- 12. NO TREES ARE PERMITTED WITHIN THE RIGHT-OF-WAY SIGHT-VISIBILITY EASEMENTS AND NO TEMPORARY OR PERMANENT OBJECT, STRUCTURE OR LANDSCAPING SHALL EXCEED TWENTY FOUR INCHES IN HEIGHT WITHIN THE RIGHT-OF-WAY SIGHT-VISIBILITY EASEMENTS.
- 13. "RANCHO EL DORADO PHASE III HOMEOWNERS ASSOCIATION, AN ARIZONA NON-PROFIT CORPORATION WILL BE FORMED AND THE CC&R'S WILL BE RECORDED IN CONJUNCTION WITH THE FINAL PLAT FOR THIS SUBDIVISION."
- 14. A ½ INCH CAPPED REBAR SHALL BE SET AT ALL LOT, TRACT, AND PARCEL CORNERS UPON THE COMPLETION OF PAVING IMPROVEMENTS.

OWNER OF RECORD:

CITY OF MARICOPA, AN ARIZONA MUNICIPAL CORPORATION 39700 WEST CIVIC CENTER PLAZA MARICOPA, ARIZONA 85138 (520) 568-9098

REFERENCE DOCUMENTS

(R1) RANCHO EL DORADO PHASE III-PARCEL 33, CABINET F, SLIDE 187 PCR

BASIS OF BEARINGS

THE WEST LINE OF THE SOUTHWEST QUARTER OF SECTION 13, TOWNSHIP 4 SOUTH, RANGE 3 EAST OF THE GILA AND SALT RIVER MERIDIAN, PINAL COUNTY ARIZONA, THE BEARING OF WHICH IS: NORTH OO DEGREES OF MINUTES 11 SECONDS WEST

DEPARTMENT APPROVALS

APPROVED:	
DEVELOPMENT SERVICES DIRECTOR CITY OF MARICOPA, ARIZONA	DATE

APPROVED:	
CITY ENGINEER	DATE

COUNCIL OF THE CITY OF	MARICOPA, ARIZONA, THIS _	DAY
 \YOR	DATE	
TY CLERK	DATE	

CERTIFICATION

I, MICHAEL D. POLLOCK CERTIFY THAT THIS PLAT IS CORRECT AND ACCURATE AND THE MONUMENTS DESCRIBED HEREIN HAVE EITHER BEEN SET OR LOCATED AS DESCRIBED TO THE BEST OF MY KNOWLEDGE AND BELIEF

REGISTERED LAND SURVEYOR DATE

MICHAEL D. POLLOCK RLS EPS GROUP INC. 1130 N. ALMA SCHOOL ROAD, SUITE 120 MESA AZ, 85201 WWW.EPSGROUPINC.COM

45378 MICHAEL D. POLLOCK

20-1536 MLD

ial 8-1-1 or 1-800-STAKE-IT (782-5 In Maricopa County: (602)263-110

Drawn by:

MDP

1130 N Mesa, T:480. w w w

O

TRACT

Revisions:


RE-PLA


Sheet No. of 2

RE-PLAT TRACT Q1

"RANCHO EL DORADO PHASE III-PARCEL 33"

AS RECORDED IN CABINET F, SLIDE 187 PINAL COUNTY RECORDS, LYING WITHIN THE WEST HALF OF SECTION 13, TOWNSHIP 4 SOUTH, RANGE 3 EAST, GILA AND SALT RIVER MERIDIAN, CITY OF MARICOPA, PINAL COUNTY, ARIZONA







9 TRACT

Revisions:

^{3°} 45378 [°] MICHAEL D.

20-1536

MLD Sheet No.

of 2

LEGEND

FOUND MONUMENT (AS NOTED)

PCR PINAL COUNTY RECORDER

POC POINT OF COMMENCEMENT R/W RIGHT OF WAY PER (R1)

POB POINT OF BEGINNING

• SET 1/2" REBAR W/CAP RLS 45378

• FOUND PROPERTY CORNER (AS NOTED)